

Link to Excel file

CAPITAL REGION INTERNATIONAL AIRPORT CARGO RAMP EXPANSION (PHASE 2 & 3) AND DEICING CONTAINMENT FACILITY BID FORM - ADDENDUM 1						RS&H Michigan, Inc. Date Prepared: February 3, 2023 Prepared by: CMS RS&H Project No. 1010-0095-000			
Base Bid - Package A									
NO.		ITEM NO.		ITEM DESCRIPTION		UNIT	UNIT PRICE	QUANTITY	TOTAL AMOUNT PER ITEM
1	C-105-2.1	Mobilization (10% Max)			LSUM			1	\$ -
2	C-105-2.2	Engineer's Field Office			LSUM			1	\$ -
3	G-102-11.1	Safety and Security			LSUM			1	\$ -
4	G-102-11.2	Safety Plan Compliance Document (SPCD)			LSUM			1	\$ -
5	C-100-14.1	Contractor Quality Control Program (CQCP)			LSUM			1	\$ -
6	C-102-5.1	Installation and Removal of Silt Fence			LFT			2,370	\$ -
7	C-102-5.2	Inlet Protection			EACH			14	\$ -
8	C-102-5.3	Soil Erosion and Sedimentation Control			LSUM			1	\$ -
9	P-101-5.1	Pavement Removal			SYD			770	\$ -
10	P-152-4.1	Unclassified Excavation			CYD			31,410	\$ -
11	P-152-4.2	Undercut and Backfill			CYD			4,380	\$ -
12	P-154-5.1	Subbase Course			CYD			14,580	\$ -
13	P-154-5.2	Geotextile Fabric			SYD			43,720	\$ -
14	P-155-8.1	Lime-Treated Subgrade, 18"			SYD			43,720	\$ -
15	P-155-8.2	Lime			TON			1,540	\$ -
16	P-209-5.1	Crushed Aggregate Base Course			CYD			10,930	\$ -
17	P-304-8.1	Cement Treated Base Course, 6"			SYD			43,720	\$ -
18	P-501-8.1	Cement Concrete Pavement, 15"			SYD			43,720	\$ -
19	P-620-5.1	Airport Pavement Marking, Black			SFT			2,680	\$ -
20	P-620-5.2	Airport Pavement Marking, Yellow			SFT			1,300	\$ -
21	P-620-5.3	Pavement Marking Removal			SFT			4,320	\$ -
22	D-701-5.1	RCP, Class V, 18-Inch			LFT			260	\$ -
23	D-701-5.2	RCP, Class V, 24-Inch			LFT			430	\$ -
24	D-701-5.3	RCP, Class V, 30-Inch			LFT			510	\$ -
25	D-701-5.4	RCP, Class III, 24-Inch			LFT			60	\$ -
26	D-701-5.5	RCP, Class III, 30-Inch			LFT			230	\$ -
27	D-701-5.6	Pipe Removal			LFT			200	\$ -
28	D-705-5.1	PVC Pipe, Type PS46, Perforated, 6-Inch			LFT			3,510	\$ -
29	D-705-5.2	PVC Pipe, Type PS46, Non-Perforated, 6-Inch			LFT			350	\$ -
30	D-705-5.3	Underdrain Cleanout			EACH			17	\$ -
31	D-705-5.4	Underdrain Demolition			LFT			430	\$ -
32	D-705-5.5	Underdrain Cleanout Demolition			EACH			4	\$ -
33	D-751-5.1	Stormwater Inlet and Valve Structure			EACH			1	\$ -
34	D-751-5.2	Aircraft Rated Inlet			EACH			6	\$ -
35	D-751-5.3	MDOT Standard Catch Basin with Grate, 4' Diameter			EACH			1	\$ -
36	D-751-5.4	MDOT Standard Catch Basin with Grate, 5' Diameter			EACH			1	\$ -
37	D-752-5.1	Concrete Mitered End Section, 30-Inch			EACH			1	\$ -
38	T-901-5.1	Seeding			ACRE			10	\$ -
39	T-905-5.1	Topsoiling, Obtained On-Site			CYD			3,570	\$ -
40	T-908-5.1	Mulching			ACRE			10	\$ -
41	L-105-7.1	Remove Taxiway Edge Light and Base Can			EACH			12	\$ -
42	L-105-7.2	Remove Taxiway Retroreflective Edge Marker			EACH			24	\$ -
43	L-105-7.3	Demolish Junction Can			EACH			4	\$ -
44	L-105-7.4	Temporary Airport Lighting			LSUM			1	\$ -
45	L-108-5.1	No. 8 AWG, 5 kV, L-824, Type C Cable, Installed in Trench, Duct Bank or Conduit			LFT			510	\$ -
46	L-108-5.2	No. 6 AWG, Solid, Bare Copper Counterpoise Wire, Installed Above the Duct Bank or C			LFT			450	\$ -

47	L-108-5.3	No. 4/0 AWG, THWN-2, 600 V Cable, Installed in Conduit	LFT		19,100	\$	-
48	L-108-5.4	No. 1 AWG, THWN-2, 600 V Cable, Installed in Conduit	LFT		2,880	\$	-
49	L-108-5.5	No. 6 AWG, THWN-2, Ground Cable, Installed in Conduit	LFT		3,700	\$	-
50	L-109-7.1	Power and Control Building Modification	LSUM		1	\$	-
51	L-110-5.1	Remove Existing Cable and Conduit	LSUM		1	\$	-
52	L-110-5.2	Remove Existing Cable, Existing Conduit to Remain	LSUM		1	\$	-
53	L-110-5.3	Directional Drilled Electrical Duct Bank, 1-Way, 2-Inch Schedule 40 PVC	LFT		170	\$	-
54	L-110-5.4	Direct Buried Electrical Conduit, 1-Way, 3-Inch Schedule 40 PVC	LFT		1,500	\$	-
55	L-115-5.1	L-867D Junction Can, in Turf	EACH		2	\$	-
56	L-115-5.2	Vehicle Rated Handhole	EACH		1	\$	-
57	L-125-5.1	L-853 Taxiway Retroreflective Edge Marker	EACH		15	\$	-
58	265619-1	Remove and Relocate 50' High Mast Light Pole with Three Fixtures	EACH		2	\$	-
59	265619-2	50' High Mast Light Pole with Three Fixtures	EACH		6	\$	-
BASE BID - PACKAGE A TOTAL PRICE						\$	-
Base Bid - Package B							
60	C-105-2.1	Mobilization (10% Max)	LSUM		1	\$	-
61	G-102-11.1	Safety and Security	LSUM		1	\$	-
62	P-152-4.1	Unclassified Excavation	CYD		5,240	\$	-
63	T-901-5.1	Seeding	ACRE		2	\$	-
64	T-905-5.1	Topsoiling, Obtained On-Site	CYD		1,100	\$	-
65	T-908-5.1	Mulching	ACRE		2	\$	-
66	DX-100-5.1	8" HDPE Sanitary Sewer Pipe, Installed Under Turf	LFT		1,560	\$	-
67	DX-100-5.2	8" HDPE Sanitary Sewer Pipe, Installed Under Pavement	LFT		70	\$	-
68	DX-100-5.3	10" HDPE Sanitary Sewer Pipe, Installed Under Turf	LFT		250	\$	-
69	DX-100-5.4	Sanitary Sewer Manhole	EACH		6	\$	-
70	DX-100-5.5	Sanitary Sewer Butterfly Valve	EACH		3	\$	-
71	DX-100-5.6	HDPE Flared End Section	EACH		1	\$	-
72	DX-100-5.7	Trailer Mounted Pump with 6" Discharge	EACH		1	\$	-
73	DX-200-5.1	30 mil HDPE Pond Liner	LSUM		1	\$	-
74	DX-200-5.2	30 mil HDPE Pond Cover	LSUM		1	\$	-
75	D-751-5.5	Deicer Management Pond Outfall Structure	EACH		1	\$	-
BASE BID - PACKAGE B TOTAL PRICE						\$	-