

Summary of Changes

Project: Port Lansing Site Readiness | QuestionCDN Project #10267490

Plan Issuance: Addendum #2

Date: July 15, 2026

Prepared By: Kimley-Horn of Michigan

Purpose

This Summary of Changes has been prepared to document revisions, clarifications, and updates associated with the Port Lansing Site Readiness project Addendum #2. The intent is to provide a clear record of modifications made during the current review or coordination period and to identify items requiring continued attention as a part of the Bid Questions received by 7/15/26.

Summary of Changes

Project Manual – Addendum #2 Dated 07/15/26

Page 13 – Bid schedule

- Duplicate Hydrant Gate Valves removed (Qty. 5)
- Line item P04 description changed to match plans.
- Line Item P15 – Mobilization/Demobilization added (1 EA)
- Item WW8 – Directional Drill changed from 2 EA to 268 LF per plans.
- Item WW4 and WW5 – Forcemain broken out to HDPE and PVC for directional drilling
- Item D10 – Storm Structure Removal added to schedule (Qty. 4 EA)
- Item D11 – Storm Sewer Removal added to schedule (Qty. 442 LF)

Plan Changes – Addendum #2 Dated 07/15/26

Sheet C4.1

- Directional drill limits now shown as HDPE
- Couplings labeled on either end for the PVC to HDPE Connection

Sheet C4.3

- Directional drill limits now shown as HDPE
- Couplings labeled on either end for the PVC to HDPE Connection

Sheet C4.6

- Directional drill limits now shown as HDPE
- Couplings labeled on either end for the PVC to HDPE Connection

Sheet C7.2

- Sanitary Air Release Valve detail added to the plans.

Sheet C7.3

- Additional Lift Station detail added for clarification.

Additional Documentation – Addendum #2 Dated 07/15/26

- Sanitary Forcemain specifications added to the response to questions.